3.	Supplying and running 3 phase mains in 2" W.I. pipe using No. 3-0 B. and S. insulated wire and accessories	Ft. 5
4.	Supplying, fixing and wiring a teak wood board $2\frac{1}{2}" \times 3\frac{1}{2}" \times 1"$ with battens rear board, supported on a suitable angle iron frame work equipping the board with 11 single pole iron clad 60 amps. cut outs, using No. 3-0 and 4 B. and S. insulated wires and accessories	No. 1
5.	Supplying and laying No. 4 B. and S. 3-conductor, paper insulated, lead covered, double steel tape armoured, jute served underground cable, 1,000 volts pressure, in a trench 3' deep surrounding the same with 3" fine sand and enclosing the ends in indoor type junction boxes filled with insulating compound using $1\frac{1}{2}"$ W.I. pipe No. 4 B. and S. insulated wires and accessories	Ft. 260
6.	Supplying, fixing and wiring in 3-way teakwood casing treated with two coats of Shellac varnish for switch points using D.P. 30 amps. iron clad switch with fuses, $12" \times 12" \times 1"$ teak wood board with back board, battens, No. 6 and 8 B. and S. Megohms grade insulated wires for main and tap respectively	No. 6
7.	Do do for D.P. 20 amps. iron clad switches as per specification above	„ 3
8.	Do do for Instantaneous Water Heaters, 40 amp. with nickle plated bends, back plate, etc., controlled by a 30 amp. D.P. iron clad switch with fuses mounted on a suitable T.W. board, etc., using No. 8 B. and S. 2,500 Megohms grade insulated wire .. .. (Instantaneous Water Heater will be supplied departmentally.)	
9.	Supply of Heater cord No. 10 B. and S. Twin asbestos covered and braided.	Ft. 120
10.	Earthing	L.S.

M. HAYATH,
Superintendent.

MYSORE RAILWAYS.

OFFICE OF THE CHIEF STORE-KEEPER, MYSORE SOUTH.

Notice dated 3rd August 1937.

Tenders are invited for the purchase of one typewriter, Remington No. 12 (Firm's Sl. No. L. D. 37245), automatic ribbon movement, second-hand, in working order with base-board and cover complete. The machine may be inspected at the Railway Central Stores Depot, Mysore South, during working days between 7-30 to 11-30 A.M. and 2 to 4-30 P.M. Tenders in covers sealed and superscribed "Tender for the purchase of typewriting machine," should reach this office before 4 P.M. on 30th August 1937. Offers below Rs. 75 are not likely to receive any consideration.

A. SADASIVAN,
Chief Store-Keeper.

OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, MYSORE.

Notification dated 14th August 1937.

1. Sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range Mysore, upt o 12 NOON on 27th August 1937, for constructing Seetha-Ranga Out-Patient Dispensary for the New Cheluvamba Maternity Hospital, Mysore.

2. Tenders in the prescribed form obtainable from the Office of the Assistant Engineer, Headquarter Range, Mysore, on payment of rupee one for each form, should be addressed to the Assistant Engineer, Headquarter Range, and should be superscribed as "Tender for constructing Seetha-Ranga Out-Patient Dispensary for the New Cheluvamba Maternity Hospital at Mysore." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 1,000 only in cash or Government Security, Municipal Debentures, Post Office Cash Certificates, (at cash payment value at the time of deposits and not face value) as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. (Cash amount will not carry any interest.) In case of the acceptance of the tender, an addition of the five per cent of the estimated amount as security deposit should be paid at the time of executing the agreement in the Public Works Department Form.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 27th August 1937, at 4 P.M. The final acceptance of the tender will rest with the Superintending Engineer who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever, for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Assistant Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Assistant Engineer, Headquarter Range, Mysore, on all working days between 11 A.M. and 5 P.M.

8. Specific rate should be given for each item in the Schedule, and the rates should be in rupees, annas and in multiples of three pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Assistant Engineer, Headquarter Range, Mysore, and approved by the Superintending Engineer shall be final and legally binding on the tenderer.

15. The quantities as estimated are only approximate and are liable to alterations, omissions, deductions or additions, at the discretion of the Assistant Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and handed over to the Public Works Department by the end of August 1938, failing which the Assistant Engineer may, at his discretion, levy a penalty up to Rs. 50 per day, which will be recovered from the contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief Engineer shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Assistant Engineer, Headquarter Range, Mysore.

19. No claims for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will however be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery, that will be supplied by the Assistant Engineer, in the interest of the work, shall be accepted by the tenderer at the rates fixed by the Assistant Engineer and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractors should arrange for the payment of Royalty and Tolls.

Note.—(A) The contractor should at his own cost—

(1) provide rods, stakes, ropes and labours required in setting out the works,
(2) provide all necessary scaffolding, centering labour and appliance for hoisting,
(3) provide mortar mill and shed to keep materials under cover and also for workmen,
(4) arrange for protecting work during inclement weather,
(5) supply requisite temporary lights, water cisterns, water-shoots, coverings to masonry, tile pieces to steps, sieves, parahs or measures, shoring and other requisite protection during the progress of the work,
(6) supply all water required for work and workmen and shall provide latrines, drainages, etc.,
(7) clean away all dirt, rubbish, superfluous materials and debris as they accumulate,
(8) provide arrangements for pumping and bailing from excavations and foundations, wherever and whenever necessary with their own pumping apparatus, including necessary leading drains, slump pits, etc.,

(9) wash floors at completion and leave the whole of the work and premises in a clean and orderly condition, etc.,

(10) afford facilities to any other parties employed upon the work, so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.

Note.—(B) It is the business of the Contractors to make their own arrangements for the quarries and supplies of materials.

23. The rates for wood-work for all works quoted should be based on the rates of the departmental supply as noted below. Only Mysore Teak, selected from the Mysore Government Depots must be used.

24. Work to the extent of Rs. 5,000 will have to be carried out each month.

Prevailing Government rates at Mysore Forest Depot for Mysore teak is as follows :—

	Rs.	a.	p.	
(1) Selected 1st class logs	2	8	0	per c.ft.
(2) Cut scantling of sizes 3″×4″ ..	3	4	0	,,
(2) (*a*) Do 3″×5″ to 4″×7″ ..	3	12	0	,,
(3) Planks 1″ to 1¾″ to required sizes ..	4	8	0	,,

Abstract of estimated quantities for constructing Seeth Ranga Out-Patient Dispensary for the proposed New Cheluvamba Maternity Hospital at Mysore.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavation in hard gravelly soil and filling in basement with watering and tamping, etc., complete	C.yds.	..	244	
2	Filling in foundation with broken granite stone jelly concrete in lime mortar, in layers not more than 6″ thick including watering and tamping	C.ft.	..	1,837	
3	Filling in foundation with size stone in lime mortar including through bond at every 6 ft.	,,	..	3,714	
4	Size stone in lime mortar for basement with through bond stones 6′ apart including all quoins neatly dressed 2″ wide	,,	..	1,402	
5	Burnt brick in lime mortar for superstructure ..	,,	..	5,904	
6	Burnt stone slabs 6″ thick, two lines dressed and fixed in mortar	S.ft.	..	330	
7	Cement concrete slabs (1 : 2 : 4) 4″ thick including fixing on mortar bed	C.ft.	..	455	
8	Granite cut stone square pillars 9″×9″×10′, including base and as per design neatly dressed and fixed complete	Each	..	16	
9	Do do half pillars at wall ends 6″×9″×10′ including base and caps, etc., complete	,,	..	2	
10	Providing and fixing R. S. girders of B.S.S. (tested) including hoisting including one coat of anticorrosive paint, etc., complete	Cwt.	..	129·28	
11	× met partition wall with burnt brick in cement mortar with × met at every third course including chunam plastering complete ..	S.ft.	..	963	
12	R.C.C. terrace for spans not exceeding 10 ft. with reinforcement complete 4″ to 6″ thick with 3″ kappi on top and two courses of flat tiles including top and ceiling plastering and white-washing with coving as per design, etc., complete	Sqr.	..	48·05	
13	Constructing parapet wall with burnt brick in lime mortar 9″×2½″ as per required design including plastering and white or colour washing, etc., complete	R.ft.	..	230	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
14	Constructing balustraded parapet wall with cement concrete with reinforcements, etc., complete	R.ft.	..	96	
15	Constructing parapet wall in front verandah and court-yard with burnt brick in mortar, 9″×2′ as per required design including plastering, white or colour washing, etc., complete ..	R.ft.	..	129	
16	Providing and fixing teakwood door of frames 3″×5″ without bottom sills having $\frac{1}{3}$ panelled and $\frac{2}{3}$ galzed shutters $1\frac{1}{2}$″ thick with teakwood rectangular ventilators on top including Acme brass fittings and superior rim lock with handles, three finger plates 12″×4″ as per design with 6″ brass hinges and two 6″ hooks, brass screws, barrel bolts of suitable size, etc., complete	S.ft.	..	324	
17	Do do doors in × met partition walls with frames 3″×4″ and shutters of $\frac{2}{3}$ glazed and $\frac{1}{3}$ panelled and other details as per item 16	S.ft.	..	201	
18	Providing and fixing T. W. windows with 3″×5″ frames and $1\frac{1}{4}$″ thick glazed shutters opening outside in halves and top ventilators ($1\frac{1}{2}$′×$3\frac{1}{2}$′) including brass, hinges, hooks, 2″ rings and casement adjusting stays, etc., complete	S.ft.	..	420	
19	Do do without two ventilators and fully glazed shutters four folded outside with parliamentary hinges and other details as per item 16 above	,,	..	60	
20*a*	Providing and fixing T. W. ventilators 2′×2′ with glazed shutters inside including superior brass fittings, etc., complete	,,	..	24	
b	Providing and fixing teakwood ventilators with glazed shutters as per required design with brass and iron fixtures, etc., complete ..	,,	..	120	
21	Providing T. W. wall shelves with $\frac{1}{3}$ panelled and $\frac{2}{3}$ glazed shutters $\frac{1}{2}$″ thick including four cross planks of $1\frac{1}{2}$″ thick 1 ft. wide with superior brass locks, handles and brass fittings etc., complete	,,	..	42	
22	Providing and fixing T. W. doors in × met partition wall with 3″×4″ frames and shutters fully panelled with springed hinges, brass fittings, etc., complete	S.ft.	..	22	
23	Plastering with chunam mortar smooth, including rounding of corners (convex corners being of cement mortar 1 : 4) for a width of 3″ both sides and the plaster on outer face being ground with yellow ochre to a cream tint	Sqr.	..	92·98	
24	White and colour washing two coats ..	,,	..	92·98	
25	Cement pointing to basement	,,	..	3·98	
26	Painting two coats with superior de Lux paint or other approved tint	,,	..	14·03	
27	Boxing up girders 12″×2″ and 3″×5″ with terraced bricks in cement mortar and reinforcements with galvanized steel-tex tied from above and chunam plastering, white-washing etc., complete	R.ft.	..	337	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
28	Flooring with 1½″ cement concrete (1 : 2 : 4) jelly to be of granite metal, over 3″ lime concrete with topping of red cement ¼″ thick finished with ironite 2½ lbs. per square and cut to tile pattern where required with all corners rounded, etc., complete ..	Sqr.	..	28.94	
29	Cast iron rain water down take pipes 4″ dia. with gratings, heads, elbows, bends, etc., with required colour painting with necessary fixtures, etc., complete including fixing ..	R.ft.	..	216	
30	Providing steel collapsible gate in rear with angle iron frames including fixing with two coats of aluminium paint complete ..	S.ft.	..	39	
31	Teak wood semi-circular fan lights with glazed shutters as per design complete	,,	..	12	
32	Constructing semi-circular arch with burnt brick in lime mortar	C.ft.	..	32	
33	Providing and fixing cast iron railings in front verandah 2 ft. high as per required design and painting, etc., complete	R.ft.	..	12	
34	Distemper wash or white lead painting to walls and doors of water closets	Sqr.	..	5.00	
35	Reinforced cement concrete Chajja 4½″ to 6″ thick as per design, etc., complete ..	R.ft.	..	138	
36	Green coloured cement band alround as per required design and specification	,,	..	358	
37	Cement concrete fret work with reinforcements as per design and specification, etc., complete	S.ft.	..	56	

M. A. RAMANUJAM,
Assistant Engineer.

PRIVATE ADVERTISEMENTS

IN THE COURT OF THE PRINCIPAL SUB-JUDGE AT BANGALORE.

Miscellaneous Application No. 239 *of* 1936-37.

(1) Chikkahonniah, (2) Gaviappa, residing in Kanakuppe, Hebbore Hobli, Tumkur Taluk .. .. *Petitioners.*

vs.

Nil .. .. *Opponents.*
In the matter of the estate of Puttiah .. .. *Deceased.*

Whereas the petitioners abovenamed, residents of Kanakuppe, Tumkur Taluk, claiming to be the brothers of the said Puttiah, deceased, have applied to this Court for a certificate under Regulation VII of 1901, to collect debts payable in respect of the estate of Puttiah, deceased, resident of Mysore Road, Bangalore City.

Notice is hereby given of the said application and all claimants in the estate of the said Puttiah, deceased, are invited to appear in this Court on the 3rd day of September 1937, when the petition of the said petitioners will be heard, and the right to the certificate will be determined.

Given under my hand and the seal of the Court, this 9th day of August 1937.

Miscellaneous Applictaion No. 259 *of* 1936-37.

(1) J. Santhosamma, wife of Bagyanathan, residing at No. 4, Lal-Bagh Road, Parappa's Compound, Bangalore City, (2) Puttaraju, (3) Kamalakaran, 2 and 3 are minors by next friend first petitioner .. .. *Petitioners.*

vs.

(1) Dr. D. John, Jassin Buildings, Byculla Station Road, Bombay, (2) C. John, No. 4, Lal-Bagh Road, Bangalore City, (3) Karupamma, Chamarajpet, Chikballapur .. .. *Opponents.*
In the matter of the estate of Bagyanathan .. .. .. *Deceased.*

Whereas J. Santhosamma, applicant, resident of No. 4, Lal-Bagh Road, Parappa's Compound, Bangalore City, claiming to be the wife of the said Bagyanathan, deceased, has applied to this Court